
US14

STREET SIDE






CURB LINE

		RNTA / RTA	SNTA /SNTAR	RNTS / RTS	SNTS
This Template was created for the following size poles	Template	Round Alum. (in.)	Sq. Alum. (in.)	Round steel (in.)	Square steel (in.)
	US09	N/A	N/A	4	4
	US10	4	4	4	4
	US11	N/A	N/A	4	4
	US12	5	5	5, 6, 7, 8, 8.5	5,6
	US13	6, 6.63, 7, 8	6	6, 7, 8, 9	6
	US14	N/A	N/A	6, 9	6
	US15	N/A	N/A	9	N/A
	US16	N/A	N/A	N/A	8

Pole Dia. or Sq.	Conduit Dia. Max.	
4"	3.5"	Whe
5"	4.5"	
6"	5.5"	D
6.63"	6"	recc
7"	6.5"	h Condu
8"	7.5"	
8.5"	8"	
9"	8.5"	

en in doubt the smaller Diameter ommended nere, for luit Dia. Max.


SIDEWALK SIDE



BOLT PROJECTION:

for 3/4" Dia. bolts.....(min. - max.) 3.25" - 3.75" for 1" Dia. bolts.....(min. - max.) 4.00" - 4.50" for 1 1/4" Dia. bolts.....(min. - max.) 4.25" - 4.75" for 1 1/2" Dia. bolts.....(min. - max.) 4.75" - 5.50"

- 1- This template prints on "D" size paper 22" x 34" (large printers/plotters recommended) Printer must be set to 100% scale for accurate dimensions. To confirm printout is to full scale, please set your measuring tape next to 12" ruler below and confirm print is to scale.
- 2- For proper footing/foundation size, we recommend consulting a local Structural Engineer. Improperly designed footing/foundation can lead to unsatisfactory performance.
- **3-** Bolt projection (min. to max.) is based on a maximum floor slope of 3°. If floor exceeds 3° slope, it is essential to increase the bolt projection length accordingly.
- 4- When grouting up to the base of the pole, if necessary, please adjust the bolt projection to accommodate for grouting.





660 W. AVENUE O, PALMDALE, CA. 93551 (661) 233-2000 FAX NO. (661) 233-2001 www.usaltg.com

